

File No: SEAC/HR/2024/023

Government of India

Ministry of Environment, Forest and Climate Change (Issued by the State Environment Impact Assessment Authority(SEIAA), HARYANA)



Date 02/07/2024



To,

Signature Global Business Park Private Limited & Fantabulous Town Developers Pvt. Ltd in collaboration with Signature Global Business Park Private Limited

13th Floor, Gopal Dass, Bhawan, 28, Barakhamba Road, Connaught Place, NEW DELHI, DELHI, 110001

singature.buss@gmail.com

Subject:

Environment Clearancefor Mix Land Use Project (90% Residential & 10% Commercial) under Transit Oriented Development Policy of DTCP, Haryana over an area measuring 16.65625 acres in the Revenue Estate of Village-Gadauli Kalan, Sector-37D, Gurugram Manesar Urban Complex, District-Gurugram, Haryana

Sir/Madam,

This has reference to your Proposal No. SIA/HR/INFRA2/459693/2024 dated 24.01.2024 and subsequent letter dated 08.02.2024 for obtaining Environmental Clearance under Category 8(b) of EIA Notification dated 14.09.2006 along with submission of due Scrutiny fee (as applicable) of 2.00.000/vide DD No. 003676 dated 13.12.2023 (in compliance of Haryana Government, Environment & Climate Change, Department Notification No. DE&CCH/3060 dated 14.10.2021). The proposal has been appraised as per prescribed procedure in the light of provisions under the EIA Notification, 2006 on the basis of the mandatory documents enclosed with the application viz., Form-1, Form1-A, Conceptual Plan, EIA/EMP Report on the basis of approved TORand additional clarifications furnished in response to the observations of the State Expert Appraisal Committee (SEAC) constituted by MoEF& CC, GoI vide their Notification dated 21.02.2022, in its 286thmeeting held on 07.02.2024 awarded "Gold" rating / grading to the Project

2. The particulars of the proposal are as below:

(i) EC Identification No.

(ii) File No.

(iii) Clearance Type

(iv) Category

(v) Project/Activity Included Schedule No.

(vii) Name of Project

EC24B3813HR5231281N

SEAC/HR/2024/023

Fresh EC

B1

8(b) Townships/ Area Development Projects /

Rehabilitation Centres

Mix Land Use Project (90% Residential & 10% Commercial) under TOD Policy over an area

measuring 16.65625 acres in the revenue estate of Village-Gadauli Kalan, Sector-37D, Gurugram Manesar Urban Complex, District-Gurugram, Haryana by M/s Signature Global Business Park

Pvt. Ltd.

SIGNATUREGLOBAL BUSINESS PARK

PRIVATE LIMITED

(ix) Location of Project (District, State) GURUGRAM, HARYANA

(x) Issuing Authority SEIAA

(xi) Applicability of General Conditions as per

(viii) Name of Company/Organization

EIA Notification, 2006

No

3. It is inter-alia, noted that the project involves in the Environment Clearance for Mix Land Use Project (90% Residential & 10% Commercial) under Transit Oriented Development Policy of DTCP, Haryana over an area measuring 16.65625 acres in the Revenue Estate of Village-Gadauli Kalan, Sector-37D, Gurugram Manesar Urban Complex, District-Gurugram, Haryana.

4. The basic details of project are as under:

	Particulars		
Online P	ropo <mark>sal no. SIA/HR/IN</mark> FRA2/459693/2024	~ 0'	
	Latitude	28°26'36.44"N	
	Longitude	76°58'5.74"E	
	Plot Area	67,405.452 m2 (16.6566 Acres)	
	Proposed Ground Coverage	36,249.174m ²	
	Proposed FAR	213492.333 m ²	
	Non FAR Area	1,73,309.709m ²	
	Total Built Up area	3,86,802.042 m ²	
	Total Green Area with Percentage	13,481.09 m ² (20% of the plot area)	
	Rainwater Harvesting Tanks (with capacity)	3 no. of tank is proposed of 980 KL capacity	
	STP Capacity	740 KLD	
	Total Parking	3,357 ECS	
	Maximum Height of Building	154.15 M	
	Power Requirement	8,512.2 kW	
	No. of DG set	6 DG sets of total capacity 8000 kVA (2 Nos. of	
	No. of DG set	6 DG sets of total capacity 8000 kVA (2 Nos. 1,000 kVA & 4 Nos. of 1,500 kVA)	
	No. of DG set Total Water Requirement	6 DG sets of total capacity 8000 kVA (2 Nos. 1,000 kVA & 4 Nos. of 1,500 kVA) 816 KLD	
	No. of DG set Total Water Requirement Fresh Water Requirement	6 DG sets of total capacity 8000 kVA (2 Nos. 1,000 kVA & 4 Nos. of 1,500 kVA) 816 KLD 557 KLD	
	No. of DG set Total Water Requirement Fresh Water Requirement Domestic Water Requirement	6 DG sets of total capacity 8000 kVA (2 Nos. 1,000 kVA & 4 Nos. of 1,500 kVA) 816 KLD 557 KLD 714 KLD	
	No. of DG set Total Water Requirement Fresh Water Requirement Domestic Water Requirement Treated water	6 DG sets of total capacity 8000 kVA (2 Nos. 1,000 kVA & 4 Nos. of 1,500 kVA) 816 KLD 557 KLD 714 KLD 548 KLD	
	No. of DG set Total Water Requirement Fresh Water Requirement Domestic Water Requirement Treated water Waste Water Generated	6 DG sets of total capacity 8000 kVA (2 Nos. 1,000 kVA & 4 Nos. of 1,500 kVA) 816 KLD 557 KLD 714 KLD 548 KLD 609 KLD	
	No. of DG set Total Water Requirement Fresh Water Requirement Domestic Water Requirement Treated water Waste Water Generated Solid Waste Generated	6 DG sets of total capacity 8000 kVA (2 Nos. 1,000 kVA & 4 Nos. of 1,500 kVA) 816 KLD 557 KLD 714 KLD 548 KLD 609 KLD 4,484 kg/day	
	No. of DG set Total Water Requirement Fresh Water Requirement Domestic Water Requirement Treated water Waste Water Generated Solid Waste Generated Biodegradable Waste	6 DG sets of total capacity 8000 kVA (2 Nos. 1,000 kVA & 4 Nos. of 1,500 kVA) 816 KLD 557 KLD 714 KLD 548 KLD 609 KLD 4,484 kg/day 2690.4 kg/day	
	No. of DG set Total Water Requirement Fresh Water Requirement Domestic Water Requirement Treated water Waste Water Generated Solid Waste Generated Biodegradable Waste Organic Waste Converter	6 DG sets of total capacity 8000 kVA (2 Nos. 1,000 kVA & 4 Nos. of 1,500 kVA) 816 KLD 557 KLD 714 KLD 548 KLD 609 KLD 4,484 kg/day 2690.4 kg/day	
	No. of DG set Total Water Requirement Fresh Water Requirement Domestic Water Requirement Treated water Waste Water Generated Solid Waste Generated Biodegradable Waste Organic Waste Converter Number of Towers	6 DG sets of total capacity 8000 kVA (2 Nos. 1,000 kVA & 4 Nos. of 1,500 kVA) 816 KLD 557 KLD 714 KLD 548 KLD 609 KLD 4,484 kg/day 2690.4 kg/day	
	No. of DG set Total Water Requirement Fresh Water Requirement Domestic Water Requirement Treated water Waste Water Generated Solid Waste Generated Biodegradable Waste Organic Waste Converter Number of Towers Basement	6 DG sets of total capacity 8000 kVA (2 Nos. 1,000 kVA & 4 Nos. of 1,500 kVA) 816 KLD 557 KLD 714 KLD 548 KLD 609 KLD 4,484 kg/day 2690.4 kg/day 2 8 2	
	No. of DG set Total Water Requirement Fresh Water Requirement Domestic Water Requirement Treated water Waste Water Generated Solid Waste Generated Biodegradable Waste Organic Waste Converter Number of Towers	6 DG sets of total capacity 8000 kVA (2 Nos. 1,000 kVA & 4 Nos. of 1,500 kVA) 816 KLD 557 KLD 714 KLD 548 KLD 609 KLD 4,484 kg/day 2690.4 kg/day	

Stories		Tower 1 $(2B + G + 24 \text{ Floors})$
		Tower- $2(2B + G + 27 \text{ floors})$
		Tower- $3(2B + G + 30 \text{ floors})$
		Tower-4 $(2B + G + 33 \text{ floors})$
		Tower- $5(2B + G + 37 \text{ floors})$
		Tower-6 $(2B + G + 35 \text{ floors})$
		Tower-7 $(2B + G + 32 \text{ floors})$
		Tower-8 $(2B + G + 30 \text{ floors})$
R+U Value of N	Material used (Glass)	2.67 W/m ² deg C
Total Cost of the	e project:	173417 lakh
EMP Budget	Capital Cost	1588 Lakhs
	Recurring Cost	122.5 Lakhs
Incremental Los	adi) PM _{2.5}	0.01 g/m^3
in respect of:	ii) PM ₁₀	0.02 g/m³
	iii) SO ₂	0.01 g/m^3
	iv) NO ₂	0.4 g/m³
	v) CO	0.09 g/m^3
Status of Constr	ruction	No Construction is done at the project site
Construction Ph	ase:	100 kVA
		100 ML & Private water tankers
		~ 1
	व व्यवस्थित	1

Table -2 EMP Details

COMPONENT	CAPITAL COST (INR LAKH)	RECURRING COST (INR LAKH/YR)
Labor Sanitation & Waste water Management	30	5
Dust Mitigation Measures Including site barricading, water sprinkling & anti-smog gun)	26	6
Storm Water Management (temporary drains & sedimentation basin)	10	2.5
Solid Waste Management	5	1
TOTAL	71//	14.5

COMPONENT	CAPITAL COST (INR LAKH)	RECURRING COST (INR LAKH/YR)	
Sewage Treatment Plant	336	50	
Rain Water Harvesting System	64	20	
Solid Waste Management	20	5	
Environmental Monitoring	6	9	
Green Area/ Landscape Area	600	4	
Others (Energy saving System, miscellaneous)	256	20	
Sub-Total	1282	108	
CE	<u>R</u>	•	
Plantation in nearby School	30		
Drinking Water facilities in nearby schools	15		
Arrangement of Medical Camp	15		
Renovation work of School Near by Village	80		
Distribution of School Bags/Uniform/ and accessories	25		
Road and Others Infra development in School/Village	50		
Training/Promotion of Green Buildings technology /Environment Monitoring and Sustainability	20		

TOTAL EMP BUDGET		
COMPONENT	CAPITAL COST (INR LAKH)	RECURRING COST (INR LAKH/YR)
During Construction Phase	71	14.5
During Operation Phase	1517	108
TOTAL	1588	122.5

1517

5. In view of the recommendations made by State Expert Appraisal Committee (SEAC) in the said case and further consideration of the documents/details submitted by the Project Proponent; the Authority after discussions decided during 176th Meetingheld on 13.06.2024to "GRANT ENVIRONMENT CLEARANCE" to Signature Global Business Park Private Limited & Fantabulous Town Developers Pvt. Ltd in collaboration with Signature Global Business Park Private Limited (as per the License issued by DTCP vide Endst No.LC-5142/Asstt (RK)/2023/37272 dated 02.11.2023) under Category 8(b) of EIA Notification dated 14.09.2006 issued by the Ministry of Environment and Forest, Government of India.

Copy To

- 1. Director (IA Division), MoEF& CC, GoI, Indira Paryavaran Bhavan, Zorbagh Road- New Delhi-110003.
- 2. Chairman, State Environment Impact Assessment Authority, Bay No. 55-58, Prayatan Bhawan, Sector-2, Panchkula, Haryana
- 3. Chairman, Haryana State Pollution Control Board, C-11, Sector-6, Panchkula.

Total

- 4.Director, Environment & Climate Change Department, Haryana, SCO 1-3, Sector-17 D, Chandigarh-160017
- 5.Director General, Town & Country Planning Haryana, Plot No. 3, Sector 18A, Madhya Marg, Chandigarh- 160018.
- 6.Regional Office, Ministry of Environment, Forests & Climate Change, Govt. of India, Bay's No. 24-25, Sector 31-A, Dakshin Marg, Chandigarh-160018

Annexure 1

Specific EC Conditions for (Townships/ Area Development Projects / Rehabilitation Centres)

1. Specific Conditions

S. No	EC Conditions
1.1	Sewage shall be treated in the STP based on latest Technology with tertiary treatment i.e. Ultra Filtration to achieve standards ordered by NGT. The Treated effluent from STP shall be recycled/reused for flushing. DG cooling and Gardening. The dimension of each component of STP should be properly designed as per Norms.
1.2	The Project Proponent would devise a monitoring plan to the satisfaction of the State Pollution Control Board so as to continuously monitor the treated waste water being used for flushing in terms of faecal coli forms and other pathogenic bacteria
1.3	The PP shall ensure that total EMP Budget shall be spent on project during construction as well as during operational phase. The EMP cost on Socio Economic activities shall be used before the commencement of the project & EMP recurring inside the project shall be implemented throughout the operation of the project. The PP shall establish Environment monitoring cell as per documents submitted

S. No	EC Conditions
1.4	The Project Proponents would commission a third party study on the implementation of conditions related to quality and quantity of recycle and reuse of treated water, efficiency of treatment systems, quality of treated water being supplied for flushing (specially the bacterial counts), comparative bacteriological studies from toilet seats using recycled treated waters and fresh waters for flushing, and quality of water being supplied through spray faucets attached to toilet seats
1.5	Separate wet and dry bins must be provided in each unit and at ground level for facilitating segregation of waste. Solid Waste shall be segregated into wet garbage and inert materials. Wet Garbage shall be composted in Organic waste convertor. Adequate area shall be provided for solid waste management within the premises which will include area for segregation, composting. The Inert waste from the project will be sent to dumping site
1.6	Traffic management plan as submitted shall be implemented in letter and spirit. Apart, a detailed traffic management and traffic decongestion plan shall be drawn up to ensure that the current level of service of the roads within a 05 kms radius of the project is marinated and improved upon after the implementation of the project. This plan should be based on cumulative impact of all development and increased habilitation being carried out or purpose to be carried out by the project or other agencies in this 05kms radius of the site in different scenarios of space and time
1.7	The Project Proponent shall obtain all necessary clearance/permission from all relevant agencies including town planning authority before commencement of work. All the construction shall be done in accordance with the local building byelaws
1.8	The PP shall install the Eco Friendly Green Transformer based on ester oil to reduce the carbon foot print. The PP shall shift to gas based generator set when the gas is available. The PP shall install APCM for the DG set. The PP shall reduce the SO ₂ load by 30% if HSD is used
1.9	The PP shall install electric charging points for charging of electric vehicles
1.10	Consent to establish/operate for the expansion project shall be obtained from the State Pollution Control Board as required under the Air (Prevention and Control of pollution) Act, 1981 and the Water (Prevention and control of pollution) Act, 1974
1.11	The Approval of the Competent Authority shall be obtained for structural safety of building code due to earthquakes, adequacy of fire fightingequipments etc. as per National Building Code including protection measures from lightening etc
1.12	That Project Proponent shall ensure that Revenue Rasta shall not be obstructed or transgressed to hamper the public movement in any way. Meaning thereby, Revenue Rasta shall remain open & accessible to public as existed earlier. Any attempt to obstruct/divert the Revenue Rasta, shall invite stern action as deemed appropriate from the Competent Authority
1.13	The PP shall not carry any construction below the HT Line passing through the project, if any
1.14	The PP shall obtain the Fire NOC from the Competent Authority before taking occupation of the building
1.15	The PP shall not give occupation or possession before the water supply, sewage connection and electricity connection permitted by the competent authority

S. No	EC Conditions
1.16	The PP shall obtain the permission regarding withdrawal of ground water from CGWA before the start of the project and also obtained the CTO from HSPCB after the approval from CGWA
1.17	The PP shall carry out the quarterly awareness programs for the stakeholders of the commercial colony/project
1.18	The PP shall install Digital water level recorder for monitoring the water recharge and carry out quarterly maintenance and cleaning of RWH pits
1.19	The PP shall ensure the compliance of provisions of Plastic Waste Management (Amendment) Rules, 2022 relevant for the project
1.20	The PP may provide electric charging stations to facilitate electric vehicle commuters
1.21	The PP shall take all preventive measures including water sprinkles to control dust during construction and operational phase
1.22	Any change in stipulations of EC will lead to Environment Clearance void-ab-initio and PP will have to seek fresh Environment Clearance
1.23	The PP is required to plant 10 times trees at the project site and compensatory tree plantation will be done @1:10. No tree cutting has been proposed in the instant project. A minimum of 1 tree for every 80sqm of land should be planted and maintained. The Existing trees will be counted for this purpose. The landscape planning should include plantation of native species. The species with heavy foliage, broad leaves and wide canopy cover are desirable. Water intensive and/or invasive species should not be used for landscaping. As proposed 13,481.09 m2 (20% of the plot area)shall be provided for green area development
1.24	03 Rain Water tanks shall be provided for ground water recharging as per the CGWB norms
1.25	The PP shall provide solar power as per HAREDA norms
1.26	The PP shall install required number of Anti Smog Guns at the project site as per the requirement of HSPCB
1.27	The PP shall register themselves on https://dustapphspcb.com portal as per the Direction No. 14 dated 11.06.2021 issued regarding dust mitigation by Commission for Air Quality Management in National Capital Region and Adjoining Areas
1.28	That Project Proponent shall submitwithin one month revised green area plan so as to maintain 60% of the green area as block plantation in the project site
1.29	The Project proponent will also undertake mitigation measures during the construction period to control dust pollution
1.30	Project proponent shall install DG sets for the project as per latest Guidelines of GRAP, NCAP & CPCB

Standard EC Conditions for (Townships/ Area Development Projects / Rehabilitation Centres)

1. Statutory Compliance

S. No	EC Conditions
1.1	The project proponent shall obtain all necessary clearance/ permission from all relevant agencies including town planning authority before commencement of work. All the construction shall be done in accordance with the local building byelaws.
1.2	The approval of the Competent Authority shall be obtained for structural safety of buildings due to earthquakes, adequacy of firefighting equipment etc. as per National Building Code including protection measures from lightening etc.
1.3	The project proponent shall obtain forest clearance under the provisions of Forest (Conservation) Act, 1980, in case of the diversion of forest land for non-forest purpose involved in the project.
1.4	The project proponent shall obtain clearance from the National Board for Wildlife, if applicable.
1.5	The project proponent shall obtain Consent to Establish / Operate under the provisions of Air (Prevention & Control of Pollution) Act, 1981 and the Water (Prevention & Control of Pollution) Act, 1974 from the concerned State Pollution Control Board/ Committee.
1.6	The project proponent shall obtain the necessary permission for drawl of ground water / surface water required for the project from the competent authority.
1.7	A certificate of adequacy of available power from the agency supplying power to the project along with the load allowed for the project should be obtained.
1.8	All other statutory clearances such as the approvals for storage of diesel from Chief Controller of Explosives, Fire Department, Civil Aviation Department shall be obtained, as applicable, by project proponents from the respective competent authorities.
1.9	The provisions of the Solid Waste Management Rules, 2016, e-Waste (Management) Rules, 2016, and the Plastics Waste Management Rules, 2016, shall be followed.
1.10	The project proponent shall follow the ECBC/ECBC-R prescribed by Bureau of Energy Efficiency, Ministry of Power strictly.

2. Air Quality Monitoring And Preservation

S. No	EC Conditions
2.1	Notification GSR 94(E) dated 25.01.2018 of MoEF&CC regarding Mandatory Implementation of Dust Mitigation Measures for Construction and Demolition Activities for projects requiring Environmental Clearance shall be complied with.
2.2	A management plan shall be drawn up and implemented to contain the current exceedance in ambient air quality at the site.
2.3	The project proponent shall install system to carryout Ambient Air Quality monitoring for common/criterion parameters relevant to the main pollutants released (e.g. PM10 and PM2.5)

S. No	EC Conditions
	covering upwind and downwind directions during the construction period.
2.4	Diesel power generating sets proposed as source of backup power should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use of low sulphur diesel. The location of the DG sets may be decided with in consultation with State Pollution Control Board.
2.5	Construction site shall be adequately barricaded before the construction begins. Dust, smoke & other air pollution prevention measures shall be provided for the building as well as the site. These measures shall include screens for the building under construction, continuous dust/ wind breaking walls all around the site (at least 3-meter height). Plastic/tarpaulin sheet covers shall be provided for vehicles bringing in sand, cement, murram and other construction materials prone to causing dust pollution at the site as well as taking out debris from the site.
2.6	Sand, murram, loose soil, cement, stored on site shall be covered adequately so as to prevent dust pollution.
2.7	Wet jet shall be provided for grinding and stone cutting.
2.8	Unpaved surfaces and loose soil shall be adequately sprinkled with water to suppress dust.
2.9	All construction and demolition debris shall be stored at the site (and not dumped on the roads or open spaces outside) before they are properly disposed. All demolition and construction waste shall be managed as per the provisions of the Construction and Demolition Waste Management Rules 2016.
2.10	The diesel generator sets to be used during construction phase shall be low sulphur diesel type and shall conform to Environmental (Protection) prescribed for air and noise emission standards.
2.11	The gaseous emissions from DG set shall be dispersed through adequate stack height as per CPCB standards. Acoustic enclosure shall be provided to the DG sets to mitigate the noise pollution. Low sulphur diesel shall be used. The location of the DG set and exhaust pipe height shall be as per the provisions of the Central Pollution Control Board (CPCB) norms.
2.12	For indoor air quality the ventilation provisions as per National Building Code of India.

3. Water Quality Monitoring And Preservation

S. No	EC Conditions	
3.1	The natural drain system should be maintained for ensuring unrestricted flow of water. No construction shall be allowed to obstruct the natural drainage through the site, on wetland and water bodies. Check dams, bio-swales, landscape, and other sustainable urban drainage systems (SUDS) are allowed for maintaining the drainage pattern and to harvest rain water.	
3.2	Buildings shall be designed to follow the natural topography as much as possible. Minimum cutting and filling should be done.	

	EC Conditions
3.3 Total	I fresh water use shall not exceed the proposed requirement as provided in the project details.
3.4 recor	quantity of fresh water usage, water recycling and rainwater harvesting shall be measured and rded to monitor the water balance as projected by the project proponent. The record shall be nitted to the Regional Office, MoEF&CC along with six monthly Monitoring reports.
3.5 wate wate speci	ertificate shall be obtained from the local body supplying water, specifying the total annual or availability with the local authority, the quantity of water already committed, the quantity of or allotted to the project under consideration and the balance water available. This should be ified separately for ground water and surface water sources, ensuring that there is no impact on rusers.
3.6 Gras	east 20% of the open spaces as required by the local building bye-laws shall be pervious. Use of as pavers, paver blocks with at least 50% opening, landscape etc. would be considered as ious surface.
3.7 and	ullation of dual pipe plumbing for supplying fresh water for drinking, cooking and bathing etc other for supply of recycled water for flushing, landscape irrigation, car washing, thermal ing, conditioning etc. shall be done.
1 3 8	of water saving devices/fixtures (viz. low flow flushing systems; use of low flow faucets tap tors etc) for water conservation shall be incorporated in the building plan.
_	tration of grey and black water should be done by the use of dual plumbing system. In case of the stack system separate recirculation lines for flushing by giving dual plumbing system be
3.10	er demand during construction should be reduced by use of pre-mixed concrete, curing agents other best practices referred.
3.11 prov. Mini	local bye-law provisions on rain water harvesting should be followed. If local bye-law ision is not available, adequate provision for storage and recharge should be followed as per the istry of Urban Development Model Building Byelaws, 2016. Rain water harvesting recharge storage tanks shall be provided for ground water recharging as per the CGWB norms.
3.12 recha total feasi	ain water harvesting plan needs to be designed where the recharge bores of minimum one arge bore per 5,000 square meters of built up area and storage capacity of minimum one day of fresh water requirement shall be provided. In areas where ground water recharge is not able, the rain water should be harvested and stored for reuse. The ground water shall not be drawn without approval from the Competent Authority.
3.13 All r	recharge should be limited to shallow aquifer.
3.14 No g	ground water shall be used during construction phase of the project.
3.15 the g	ground water dewatering should be properly managed and shall conform to the approvals and guidelines of the CGWA in the matter. Formal approval shall be taken from the CGWA for any nd water abstraction or dewatering.
3.16 The	quantity of fresh water usage, water recycling and rainwater harvesting shall be measured and

S. No	EC Conditions
	recorded to monitor the water balance as projected by the project proponent. The record shall be submitted to the Regional Office, MoEF&CC along with six monthly Monitoring reports.
3.17	Sewage shall be treated in the STP with tertiary treatment. The treated effluent from STP shall be recycled/re-used for flushing, AC make up water and gardening. As proposed, no treated water shall be disposed in to municipal drain.
3.18	No sewage or untreated effluent water would be discharged through storm water drains.
3.19	Onsite sewage treatment of capacity of treating 100% waste water to be installed. The installation of the Sewage Treatment Plant (STP) shall be certified by an independent expert and a report in this regard shall be submitted to the Ministry before the project is commissioned for operation. Treated waste water shall be reused on site for landscape, flushing, cooling tower, and other end-uses. Excess treated water shall be discharged as per statutory norms notified by Ministry of Environment, Forest and Climate Change. Natural treatment systems shall be promoted.
3.20	Periodical monitoring of water quality of treated sewage shall be conducted. Necessary measures should be made to mitigate the odour problem from STP.
3.21	Sludge from the onsite sewage treatment, including septic tanks, shall be collected, conveyed and disposed as per the Ministry of Urban Development, Central Public Health and Environmental Engineering Organization (CPHEEO) Manual on Sewerage and Sewage Treatment Systems, 2013.

4. Noise Monitoring And Prevention

S. No	EC Conditions
4.1	Ambient noise levels shall conform to residential area/commercial area/industrial area/silence zone both during day and night as per Noise Pollution (Control and Regulation) Rules, 2000. Incremental pollution loads on the ambient air and noise quality shall be closely monitored during construction phase. Adequate measures shall be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB / SPCB.
4.2	Noise level survey shall be carried as per the prescribed guidelines and report in this regard shall be submitted to Regional Officer of the Ministry as a part of six-monthly compliance report.
4.3	Acoustic enclosures for DG sets, noise barriers for ground-run bays, ear plugs for operating personnel shall be implemented as mitigation measures for noise impact due to ground sources.

5. Energy Conservation Measures

S. No	EC Conditions
5.1	Compliance with the Energy Conservation Building Code (ECBC) of Bureau of Energy Efficiency shall be ensured. Buildings in the States which have notified their own ECBC, shall comply with the State ECBC.
5.2	Outdoor and common area lighting shall be LED.

S. No	EC Conditions
5.3	Concept of passive solar design that minimize energy consumption in buildings by using design elements, such as building orientation, landscaping, efficient building envelope, appropriate fenestration, increased day lighting design and thermal mass etc. shall be incorporated in the building design. Wall, window, and roof u-values shall be as per ECBC specifications.
5.4	Energy conservation measures like installation of CFLs/ LED for the lighting the area outside the building should be integral part of the project design and should be in place before project commissioning.
5.5	Solar, wind or other Renewable Energy shall be installed to meet electricity generation equivalent to 1% of the demand load or as per the state level/ local building bye-laws requirement, whichever is higher.
5.6	Solar power shall be used for lighting in the apartment to reduce the power load on grid. Separate electric meter shall be installed for solar power. Solar water heating shall be provided to meet 20% of the hot water demand of the commercial and institutional building or as per the requirement of the local building bye-laws, whichever is higher. Residential buildings are also recommended to meet its hot water demand from solar water heaters, as far as possible.

6. Waste Management

S. No	EC Conditions
6.1	A certificate from the competent authority handling municipal solid wastes, indicating the existing civic capacities of handling and their adequacy to cater to the M.S.W. generated from project shall be obtained.
6.2	Disposal of muck during construction phase shall not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.
6.3	Separate wet and dry bins must be provided in each unit and at the ground level for facilitating segregation of waste. Solid waste shall be segregated into wet garbage and inert materials.
6.4	Organic waste compost/Vermiculture pit/Organic Waste Converter within the premises with a minimum capacity of 0.3 kg/person/day must be installed.
6.5	All non-biodegradable waste shall be handed over to authorized recyclers for which a written tie up must be done with the authorized recyclers.
6.6	Any hazardous waste generated during construction phase, shall be disposed off as per applicable rules and norms with necessary approvals of the State Pollution Control Board.
6.7	Use of environment friendly materials in bricks, blocks and other construction materials, shall be required for at least 20% of the construction material quantity. These include Fly Ash bricks, hollow bricks, AACs, Fly Ash Lime Gypsum blocks, Compressed earth blocks, and other environment friendly materials.
6.8	Fly ash should be used as building material in the construction as per the provision of Fly Ash

S. No	EC Conditions
	Notification of September, 1999 and amended as on 27th August, 2003 and 25th January, 2016. Ready mixed concrete must be used in building construction.
6.9	Any wastes from construction and demolition activities related thereto shall be managed so as to strictly conform to the Construction and Demolition Waste Management Rules, 2016.
6.10	Used CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/ rules of the regulatory authority to avoid mercury contamination.

7. Green Cover

S. No	EC Conditions
7.1	No tree can be felled/transplant unless exigencies demand. Where absolutely necessary, tree felling shall be with prior permission from the concerned regulatory authority. Old trees should be retained based on girth and age regulations as may be prescribed by the Forest Department. Plantations to be ensured species (cut) to species (planted).
7.2	A minimum of 1 tree for every 80 sqm of land should be planted and maintained. The existing trees will be counted for this purpose. The landscape planning should include plantation of native species. The species with heavy foliage, broad leaves and wide canopy cover are desirable. Water intensive and/or invasive species should not be used for landscaping.
7.3	Where the trees need to be cut with prior permission from the concerned local Authority, compensatory plantation in the ratio of 1:10 (i.e. planting of 10 trees for every 1 tree that is cut) shall be done and maintained. Plantations to be ensured species (cut) to species (planted). Area for green belt development shall be provided as per the details provided in the project document.
7.4	Topsoil should be stripped to a depth of 20 cm from the areas proposed for buildings, roads, paved areas, and external services. It should be stockpiled appropriately in designated areas and reapplied during plantation of the proposed vegetation on site.

8. Transport

S. No	EC Conditions
8.1	A comprehensive mobility plan, as per MoUD best practices guidelines (URDPFI), shall be prepared to include motorized, non-motorized, public, and private networks. Road should be designed with due consideration for environment, and safety of users. The road system can be designed with these basic criteria. a. Hierarchy of roads with proper segregation of vehicular and pedestrian traffic. b. Traffic calming measures. c. Proper design of entry and exit points. d. Parking norms as per local regulation.
8.2	Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards be operated only during non-peak hours.
8.3	A detailed traffic management and traffic decongestion plan shall be drawn up to ensure that the current level of service of the roads within a 05 kms radius of the project is maintained and

S. No	EC Conditions
	improved upon after the implementation of the project. This plan should be based on cumulative impact of all development and increased habitation being carried out or proposed to be carried out by the project or other agencies in this 05 Kms radius of the site in different scenarios of space and time and the traffic management plan shall be duly validated and certified by the State Urban Development department and the P.W.D./ competent authority for road augmentation and shall also have their consent to the implementation of components of the plan which involve the participation of these departments.

9.

S. No	EC Conditions
9.1	Corporate Environment Responsibility The project proponent shall comply with the provisions of CER, as applicable
9.2	The company shall have a well laid down environmental policy duly approved by the Board of Directors. The environmental policy should prescribe for standard operating procedures to have proper checks and balances and to bring into focus any infringements/ deviation/ violation of the environmental/ forest/ wildlife norms/ conditions. The company shall have defined system of reporting infringements/ deviation/ violation of the environmental/ forest/ wildlife norms/ conditions and/ or shareholders/ stake holders. The copy of the board resolution in this regard shall be submitted to the MoEF&CC as a part of six-monthly report
9.3	A separate Environmental Cell both at the project and company head quarter level, with qualified personnel shall be set up under the control of senior Executive, who will directly to the head of the organization
9.4	Action plan for implementing EMP and environmental conditions along with responsibility matrix of the company shall be prepared and shall be duly approved by competent authority. The year wise funds earmarked for environmental protection measures shall be kept in separate account and not to be diverted for any other purpose. Year wise progress of implementation of action plan shall be reported to the Ministry/Regional Office along with the Six Monthly Compliance Report

10. Human Health Issues

S. No	EC Conditions
10.1	All workers working at the construction site and involved in loading, unloading, carriage of construction material and construction debris or working in any area with dust pollution shall be provided with dust mask.
10.2	For indoor air quality the ventilation provisions as per National Building Code of India.
10.3	Emergency preparedness plan based on the Hazard identification and Risk Assessment (HIRA) and Disaster Management Plan shall be implemented.
10.4	Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking

S. No	EC Conditions
	water, medical health care, crèche etc. The housing may be in the form of temporary structures to be removed after the completion of the project.
10.5	Occupational health surveillance of the workers shall be done on a regular basis.
10.6	A First Aid Room shall be provided in the project both during construction and operations of the project.

11. Miscellaneous

S. No	EC Conditions
11.1	The project proponent shall prominently advertise it at least in two local newspapers of the District or State, of which one shall be in the vernacular language within seven days indicating that the project has been accorded environment clearance and the details of MoEFCC/SEIAA website where it is displayed.
11.2	ii. environmental clearance shall be submitted by the project proponents to the Heads of local bodies, Panchayats and Municipal Bodies in addition to the relevant offices of the Government who in turn has to display the same for 30 days from the date of receipt.
11.3	The project proponent shall upload the status of compliance of the stipulated environment clearance conditions, including results of monitored data on their website and update the same on half-yearly basis.
11.4	The project proponent shall submit six-monthly reports on the status of the compliance of the stipulated environmental conditions on the website of the ministry of Environment, Forest and Climate Change at environment clearance portal.
11.5	The company shall have a well laid down environmental policy duly approved by the Board of Directors. The environmental policy should prescribe for standard operating procedures to have proper checks and balances and to bring into focus any infringements/deviation/violation of the environmental/forest/wildlife norms/conditions. The company shall have defined system of reporting infringements/deviation/violation of the environmental/forest/wildlife norms/conditions and/or shareholders/stake holders. The copy of the board resolution in this regard shall be submitted to the MoEF&CC as a part of six-monthly report.
11.6	A separate Environmental Cell both at the project and company head quarter level, with qualified personnel shall be set up under the control of senior Executive, who will directly report to the head of the organization.
11.7	Action plan for implementing EMP and environmental conditions along with responsibility matrix of the company shall be prepared and shall be duly approved by competent authority. The year wise funds earmarked for environmental protection measures shall be kept in separate account and not to be diverted for any other purpose. Year wise progress of implementation of action plan shall be reported to the Ministry/Regional Office along with the Six Monthly Compliance Report
11.8	The project proponent shall submit the environmental statement for each financial year in Form-V to the concerned State Pollution Control Board as prescribed under the Environment (Protection)

S. No	EC Conditions
	Rules, 1986, as amended subsequently and put on the website of the company.
11.9	The project proponent shall inform the Regional Office as well as the Ministry, the date of financial closure and final approval of the project by the concerned authorities, commencing the land development work and start of production operation by the project.
11.10	The project authorities must strictly adhere to the stipulations made by the State Pollution Control Board and the State Government.
11.11	The project proponent shall abide by all the commitments and recommendations made in the EIA/EMP reportand also that during their presentation to the Expert Appraisal Committee.
11.12	No further expansion or modifications in the plant shall be carried out without prior approval of the Ministry of Environment, Forest and Climate Change (MoEF&CC).
11.13	Concealing factual data or submission of false/fabricated data may result in revocation of this environmental clearance and attract action under the provisions of Environment (Protection) Act, 1986.
11.14	The Ministry may revoke or suspend the clearance, if implementation of any of the above conditions is not satisfactory.
11.15	The Ministry reserves the right to stipulate additional conditions if found necessary. The Company in a time bound manner shall implement these conditions.
11.16	The Regional Office of this Ministry shall monitor compliance of the stipulated conditions. The project authorities should extend full cooperation to the officer (s) of the Regional Office by furnishing the requisite data / information/monitoring reports.
11.17	The above conditions shall be enforced, inter-alia under the provisions of the Water (Prevention & Control of Pollution) Act, 1974, the Air (Prevention & Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986, Hazardous and Other Wastes (Management and Transboundary Movement) Rules, 2016, and the Public Liability Insurance Act, 1991 along with their amendments and Rules and any other orders passed by the Hon'ble Supreme Court of India / High Courts and any other Court of Law relating to the subject matter.
11.18	Any appeal against this EC shall lie with the National Green Tribunal, if preferred, within a period of 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.
11.19	The validity of this environment clearance letter is valid up to 10 years from the date of issuance of EC letter in accordance with the MoEF& CC, GoI Notification No. S.O.1807 (E), dated the 12th April, 2022. The environment clearance conditions applicable till life space project will continue to apply. In case of violation the action will be taken as per the laid down law of land. Compliance report shall be sent to this office till life of the project
11.20	If project is not completed within the validity period then the project proponent shall submit the application for extension of validity within one month before the lapse of validity period of Environment Clearance
11.21	The Project Proponent should intimate to the Authority as well as to the quarter concerned in case

S. No	EC Conditions
	of any change in the present communication address

